

BID SHEET

DELAWARE RIVER TRAIL PENN TREATY PARK TO THE BATTERY

DELAWARE RIVER TRAIL IN PHILADELPHIA COUNTY

DECEMBER 23, 2025

Line No.	Item No.	Items	Quantity	Unit	Unit Price (\$)	Amount (\$)
1	0201-0001	Clearing and Grubbing	1	Lump Sum		
2	0203-0001	Class 1 Excavation	1	Lump Sum		
3	0203-0006	Saw Cutting	64	Linear Foot		
4	0212-0014	Geotextile, Class 4, Type A	141	Square Yard		
5	0350-0104	Subbase, 4" Depth (No. 2A)	356	Square Yard		
6	0413-0195	Superpave Asphalt Mixture Design, WMA Wearing Course, PG 64-22, <0.3 Million ESALS, 9.5mm Mix SRL-L, 1.5" Depth	356	Square Yard		
7	0413-6032	Superpave Asphalt Mixture Design, WMA Binder Course, PG 64-22, <0.3 Million ESALS, 25.0mm Mix, 4" Depth	356	Square Yard		
8	0460-0002	Asphalt Tack Coat	18	Gallon		
9	0491-0012	Milling of Bituminous Pavement Surface, 1.5" Depth	97	Square Yard		
10	0606-0162	Grade Adjustment of Existing Utility Box	1	Each		
11	0608-0001	Mobilization	1	Lump Sum		
12	0641-0005	Plain Cement Concrete Curb and Gutter, 6" Height	3	Square Yard		
13	0686-0010	Construction Surveying, Type A	1	Lump Sum		

Line No.	Item No.	Items	Quantity	Unit	Unit Price (\$)	Amount (\$)
14	0810-0023	Tree Trimming to a Max Height of 20'	1	Lump Sum		
15	0810-0052	Selective Tree Removal	4	Each		
16	0811-0003	Temporary Protective Fence	126	Linear Foot		
17	0855-0003	Pumped Water Filter Bag	1	Each		
18	0860-0000	Inlet Filter Bag for Type M Inlet	1	Each		
19	0867-0012	Compost Filter Sock, 12" Diameter	552	Linear Foot		
20	0901-0001	Maintenance and Protection of Traffic during Construction	1	Lump Sum		
21	0931-0003	Post Mounted Signs, Type B, Steel Square Post	4	Square Foot		
22	0964-0002	4" Yellow Epoxy Pavement Markings	350	Linear Foot		
23	0970-0001	Remove Post Mounted Signs, Type A	1	Each		
24	9000-0001	6" White Hot Thermoplastic Pavement Marking, Rumble Strip On Trail	68	Linear Foot		
25	9000-0002	White Preformed Thermoplastic Legend, "Bicycle with Rider, 6'-0" X 3'-0"	2	Each		
26	9000-0003	White Preformed Thermoplastic Legend, "Bicycle with Rider" (4'-0" X 2'-0"), "Pedestrian" (4'-0" X 2'-0"), and "Straight Arrow" (2'-0" X 1'-0")	1	Each		
27	9000-0004	White Preformed Thermoplastic Legend, "Bikeway Turn Arrow" (4'-0" X 2'-0")	1	Each		
28	9000-0005	White Preformed Thermoplastic Legend, "Straight Arrow" (6'-0" X 1'-6")	3	Each		
29	9000-0006	White Preformed Thermoplastic Legend, Typical Yield Line Layout On Trail	3	Each		
30	9000-0007	Aggregate Bed Beneath Boardwalk	32	Cubic Yard		
31	9000-0008	Arborist Services	5000	Dollars		
32	9000-0009	Vehicle Washdown Area	2	Each		
33	9000-0010	Plain Cement 6" Concrete Header	152	Linear Foot		
34	9000-0011	Helical Piles	630	Vert. Linear Foot		
35	9000-0012	Topsoil Furnished and Placed	85	Cubic Yard		

Line No.	Item No.	Items	Quantity	Unit	Unit Price (\$)	Amount (\$)
36	9000-0013	Shrubs 5 Gal. Container	52	Each		
37	9000-0014	Perennials Planting	1383	Square Foot		
38	9000-0015	Seeding - Turf	2381	Square Foot		
39	9000-0016	PRECAST CONCRETE BOARDWALK	1	Lump sum		
40	9000-0017	Ornamental Fence Salvage and Repair, Fence Post Salvaged and Repaired, New Fence Post, and Installation	1	Lump Sum		
41	9000-0018	Steel Fixed Bollard	2	Each		
42	9000-0019	Directional Indicator Paver Block	10	Square Foot		
43	9000-0020	Salvage and Reinstall Existing Pavers	1	Lump Sum		
44	9000-0021	Concrete Unit Pavers	64	Square Yard		
45	9000-0022	Reset Existing Solar Luminaire	1	Each		
46	9000-0023	Temporary 8' Perimeter Chain Link Fence	725	Linear Foot		
47	9000-0024	Removal of Existing Retaining Wall	1	Lump Sum		
48	9000-0025	Concrete Retaining Wall	1	Lump sum		
49	9000-0026	Collapsible Bollard	1	Each		
	Total Amount Base Bid (\$)		\$			
	Total Amount in Words (Base Bid)					

SECURITY CAMERAS ADD / ALTERNATE

Line No.	Item No.	Items	Quantity	Unit	Unit Price (\$)	Amount (\$)
50	0954-0012	2 INCH CONDUIT	330	Linear Foot		
51	0954-0151	TRENCH AND BACKFILL, TYPE I	165	Linear Foot		
52	9000-0027	Composite Junction Box, 12" x 12" x 12"	2	Each		
53	9000-0028	Security Cameras & Pole	1	Lump Sum		
54	9000-0029	Security Camera Power & Fiber Feeds	1	Lump Sum		
	Total Amount ADD / ALTERNATE Bid (\$)			\$		
	Total Amount in Words (ADD / ALTERNATE BID)					